

State of Kansas



15-039-00549-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
667 8 1966
10-2-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bert Self of Self Csg. Pulling Co. has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Union Texas Petroleum,

Complete Address: 1740 Broadway, Suite B-400, Denver, Colorado.

Lease Name: Pollnow Unit Well No. 10

Location: SW-SW-SW Sec. 4 Twp. 3 Rge. (E)(W) 29

County Decatur Total Depth 3941 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

202'--8 5/8" Surface pipe, cement circulated with 175 Sx.
3939'--5 1/8" Production casing cemented with 125 Sx. Openhole completion.

Set rock and sand bridge @ 3850' and 5 Sx. cement with dump bailer. Pull 5 1/8" casing and squeeze hole with 30 sacks gel followed by 75 sacks cement.

Very truly yours,

W. L. Nichols
Conservation Division Agent