

State of Kansas



15-039-20020-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1967
8-22-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. George Waite of Solar Oil Company, has this
date requested permission to plug the following described well:

Mr. Waite guarantees payment of the plugging fee.

Operator's full Name: Solar Oil Company,

Complete Address: 1117 Union National Bldg., Wichita, Kans.

Lease Name: Amanda Well No. 3

Location: CE/2-W/2-NE Sec. 6 Twp. 3 Rge. (E)(W) 29

County Decatur Total Depth 3995' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Waite was instructed to plug the well as follows:

236'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulate hole with heavy mud, set plug @ 550' and 20 Sx. cement.

" " 230' and 20 Sx. cement.

" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

M. L. Nichols
Conservation Division Agent