

State of Kansas



15-039-00678-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 21 1966  
2-21-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ben Thompson of Santa Fe Pipe & Supply has this

date requested permission to plug the following described well:  
Union Texas Petr. Co.

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Union Texas Petroleum Company,

Complete Address: 1740 Broadway, Denver, Colorado.

Lease Name: A. Pollnow Well No. 1

Location: CSE-SE NW Sec. 5 Twp. 3 Rge. (E)(W) 29

County Decatur Total Depth 3938 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Thompson was instructed to plug the well as follows:

215'--8 5/8" Surface pipe, cement circulated.  
3938'--5 1/2" Production casing cemented with 100 Sx. Well  
plugged back to 3921'. Top perforations from 3747' to 3754'.

Push plug to 3700' and set 5 Sx. cement with dump bailer.  
Push plug to 350', set overnight bridge with 5 Sx. cement.  
Bail hole dry and fill to bottom of cellar with Redi-Mix.

Very truly yours,

Conservation Division Agent