

State of Kansas



15-039-00557-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1966
2-21-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ben Thompaon of Santa Fe Pipe and Supply has this

date requested permission to plug the following described well:
Union Texas Petr. Co.

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Union Texas Petroleum Company.

Complete Address: 1740 Broadway, Denver, Colorado.

Lease Name: Pollnow Well No. B-1

Location: SW-SW-NE Sec. 5 Twp. 3 Rge. (E)(W) 29

County Decatur Total Depth 3920 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. was instructed to plug the well as follows:

201'--8 5/8" Surface pipe, cement circulated.

3919'--5 1/2" Production casing cemented with 125 Sx. No plug back, no perforations.

Push plug to 3700' and set 5 Sx. cement with dump bailer.

Set overnight bridge @ 350' with 5 Sx. cement and fill to bottom of cellar with Redi-Mix.

Very truly yours,

W. L. Nichols
Conservation Division Agent