



15-039-20198-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company,

Complete Address: Petroleum Building, Tulsa, Oklahoma.

Lease Name: Cloyce D. Harold Well No. 1

Location: CSE-SE Sec. 36 Twp. 3 Rge. (E)(W) 29

County: Decatur Total Depth 4422' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

255'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1175'.

Circulate hole with heavy mud. Pull DP to 1600' and displace 100 Sx.
cement thru DP. Pull DP to 265' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV 25 1970

CONSERVATION DIVISION
Wichita, Kansas

11-25-70

Very truly yours,

Conservation Division Agent