



15-039-20037-00-001

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. W. W. Sauvage of W. W. Sauvage Oil Company has this date requested permission to plug the following described well:

Mr. Sauvage guarantees payment of the plugging fee.

Operator's full Name: W. W. Sauvage Oil Company,

Complete Address: Oberlin, Kansas.

Lease Name: Keith Sauvage Well No. 1

Location: SW-SW-SW Sec. 11 Twp. 3 Rge. (E)(W) 29

County: Decatur Total Depth 3945' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sauvage was instructed to plug the well as follows:

104'--8 5/8" Surface pipe, cement circulated.

Dakota section from 1300' to 1500'.

Land owner requests well to be left open as a potential fresh water well.

Circulate hole with heavy mud. Pull DP to 1525' and displace 100 Sx. cement thru DP. Pull DP to 215' and displace 30 Sx. cement thru DP. Leave top plug out at request of land owner.

RECEIVED Very truly yours,
STATE CORPORATION COMMISSION

FEB 14 1968

CONSERVATION DIVISION
Wichita, Kansas

H. L. Nichols
Conservation Division Agent

2-14-68