



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name: Enfield Well No. 1

Location: CNW-NW Sec. 19-Twp. 3 Rge. (E)(W) 35

County: Rawlins Total Depth 4225 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

328'--8 5/8" Surface pipe, cement circulated with 180 Sx.  
Top of Dakota section @ 1975'.

Circulate hole with heavy mud. Pull DP to 2200' and displace 100 Sx.  
cement thru DP. Pull DP to 335' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED  
 STATE CORPORATION COMMISSION

AUG 14 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

S-14-68

Very truly yours,

Conservation Division Agent