



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 18 1963
 11-18-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bob Barnes of Barnes & Sons Pipe Pulling has this

date requested permission to plug the following described well:
Empire Drilling Co.

Mr. Barnes guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company.

Complete Address: 650 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Bassen Well No. 1

Location: CSW SW Sec. 18 Twp. 3 Rge. (E) (W) 35

County Rawlins Total Depth 4890 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Barnes was instructed to plug the well as follows:

309' -- 8 5/8" Surface pipe, cement circulated with 125 Sx.
4768' 5 1/2" cemented with 150 Sx. Plugged back to 4470', Top
perforations 4230' to 4236'.

Send well back to 4220' and set 5 Sx cement with dump bailer.
Pull 5 1/2" to 720' and circulate heavy gel mud, pull 5 1/2" to 660'
and displace 20 Sx cement thru 5 1/2". Pull 5 1/2" to 300' and dis-
place 20 Sx cement thru 5 1/2". Pull 5 1/2", set bridge @ 30' and
10 Sx. cement to bottom of cellar.

Very truly yours,

H. L. Nichols
 Conservation Division Agent