

State of Kansas



15-193-20184-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1974 10-11-74
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Don Favinger of Abercrombie Drig., Co., Inc., has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling Company, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Wright Well No. 1

Location: NE-NE Sec. 14 Twp. 3 Rge. (E)(W) 35

County: Rawlins Total Depth 4640' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

296'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1575'.

Circulate hole with heavy mud. Pull DP to 1800' and displace 110 Cu. Ft. cement thru DP. Pull DP to 300' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent