

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 25 1972

CONSERVATION DIVISION  
Wichita, Kansas

4-25-72

15-039-20233-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Zander Well No. 1

Location 200' No. of CNW-NW Sec. 10 Twp. 3 Rge. (E) (W) 29

County Decatur Total Depth 3880'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 7:00 PM Day 21 Month 4 Year 1972

The above well was plugged as follows:

230'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 110 Cu. Ft. cement  
thru DP from 1500' to 1175'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 4-27-72

INV. NO. 5635-11