

JP
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-039-00556-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1966
CONSERVATION DIVISION
WICHITA, KANSAS
2-21-66

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Union Texas Petroleum Company,
Complete Address: 1740 Broadway, Denver, Colorado.
Lease Name Boettger Well No. 1
Location NW-NW-SE Sec. 5 Twp. 3 Rge. (E) (W)²⁹
County Decatur Total Depth 4210
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Santa Fe Pipe and Supply Company,
Address: Box # 562, Great Bend, Kansas. License No. 574
Operation Completed: Hour 11:00AM Day 12 Month 2 Year 1966

The Above well was plugged as follows:

211' --- 8 5/8" Surface pipe, cement circulated.
3913' --- 5 1/2" Production casing cemented with 125 Sx. well plugged back to
3770'. Top perforations from 3702' to 3703'.

Pushed plug to 3690' and set 5 Sx. cement with dump bailer.
Set rock bridge @ 300' and filled hole to bottom of cellar with Redi-
Mix cement. 5 to 1. (used 4 yards Redi-Mix).

I hereby certify that the above well was plugged as herein stated.

Signed: *H. D. Nichols*
Well Plugging Supervisor

INVOICED
DATE 2/21/66
INV. NO. 2955-W