

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-039-00550-0000

RECEIVED  
OCT 3 1966  
10-3-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Bulldog Pipe and Supply Company.

Complete Address: Box #1153, Tulsa, Oklahoma.

Lease Name Boettger Well No. 2

Location SE-SE-SE Sec. 5 Twp. 3 Rge. (E) (W) 29

County Decatur Total Depth 3940

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: bert Self Casing Pulling Company.

Address: R.R. #4, Hutchinson, Kansas. License No. 48

Operation Completed: Hour 11:15AM Day 27 Month 9 Year 1966

The Above well was plugged as follows:

165'--8 5/8" Surface pipe, cement circulated.  
3930'--5 1/2" Production casing cemented. Bottom hole completion.

Sanded well back to 3910' and set 5 sacks cement with dump bailer.

Pulled 5 1/2" casing and squeezed hole with 30 sacks gel followed by 75  
sacks cement. Pump-in pressure 250#. Final shut-in pressure 100#.

(Recovered 1700' 5 1/2" casing)

(Mudding and cementing operations performed by Halliburton Co.)

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 10/3/66  
INV. NO. 4037-u