

176
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00064-00-00

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 1964
8-3-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Union Texas Petroleum,

Complete Address: Drawer "D", Great Bend, Kansas.

Lease Name Pollnow Unit Well No. 3

Location NE-NE-SW Sec. 4 5 Twp. 3 Rge. (E) (W) 29

County Decatur Total Depth 3931

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Company, Incorporated,

Address: Box 221, Great Bend, Kansas. License No. 49

Operation Completed: Hour 7@00PM Day 30 Month 7 Year 1964

The Above well was plugged as follows:

271'--8 5/8" Surface pipey cement circulated. 3926'--5 1/2" # Production casing cemented with 100 Sx. Well plugged back to 3850'. Top perforations at 3746'.

Sanded well back to 3720' and set 4 Sx. cement with dump bailer. Pulled 5 1/2" to 700' and circulated heavy gel mud. Pulled 5 1/2" to 600' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 270' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge at 35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/3/64

INV. NO. 9540-W

Signed: *W. L. Dehals*
Well Plugging Supervisor