

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00549-00-00

RECEIVED
OCT 3 1966
10-3-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Union Texas Petroleum.

Complete Address: 1740 Broadway, Suite B-400, Denver, Colorado.

Lease Name Pollnow Unit Well No. 10

Location SW-SW-SW Sec. 4 Twp. 3 Rge. (E) (W) 29

County Decatur Total Depth 3941

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Bert Self Casing Pulling Company.

Address: R.R. #4, Hutchinson, Kansas. License No. 48

Operation Completed: Hour 1:15 PM Day 27 Month 9 Year 1966

The Above well was plugged as follows:

202'--8 5/8" Surface pipe, cement circulated with 175 Sx.
3939'--5 1/2" Production casing cemented with 125 Sx. Open hole completion.

Set rock and sand bridge @ 3850' and 5 sacks cement with dump bailer.

Pulled 5 1/2" casing and squeezed hole with 30 sacks gel followed by 75 sacks cement. Pump-in pressure 300#. Final shut-in pressure 200#.

(Recovered 1050' 5 1/2" casing)

(Mudding and cementing operations performed by Halliburton Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 10/3/66
INV. NO. 4036-u