

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00065-00-~~00~~  
01

RECEIVED  
STATE CORPORATION COMMISSION

OCT 3 1966  
10-3-66

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Bulldog Pipe and Supply Company.

Complete Address: Box #1153, Tulsa, Oklahoma.

Lease Name Pollnow Well No. 1

Location NE-NW-SW Sec. 4 Twp. 3 Rge. (E) (W) 29

County Decatur Total Depth 4406

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

*EDR per  
WC file  
KCC-264  
08-31-04*

Other well as hereafter indicated:     

Plugging Contractor: Bert Self Casing Pulling Company,

Address: R.R. #4, Hutchinson, Kansas. License No. 48

Operation Completed: Hour 3:30PM Day 27 Month 9 Year 1966

The Above well was plugged as follows:

195'--8 5/8" Surface pipe, cement circulated.

3961'--5 1/2" Production casing cemented. Top perforations @ 3930'.

Measured in hole with bailer and found plug @ 3950'. Sanded well back to 3910' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well with 30 sacks gel followed by 75 sacks cement. Pump-in pressure 350#. Final shut-in pressure 100#.

(Recovered 1590' 5 1/2" Casing)

(Mudding and cementing operations performed by Halliburton)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Nichols*  
Well Plugging Supervisor

DATE 10/3/66  
INV. NO. 4038-4