

KANSAS

W
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20198-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name National Associated Petroleum Company.

Complete Address Petroleum Building, Tulsa, Oklahoma.

Lease Name Cloyce D. Harold Well No. 1

Location CSE-SE Sec. 36 Twp. 3 Rge. (E) (W) 29

County Decatur Total Depth 4422'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling and Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 7:30 PM Day 18 Month 11 Year 1970

The above well was plugged as follows:

255'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1175'.

Circulated hole with heavy mud. Pulled DP to 1600' and displaced 100 Sx. cement thru
DP from 1600' to 1275'. Pulled DP to 265' and displaced 25 Sx. cement thru DP from
265' to 190'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

NOV 25 1970

CONSERVATION DIVISION
Wichita, Kansas

Signed: *M. L. Nichole*
Well Plugging Supervisor

INVOICED

DATE 11/25/70

INV. NO. 2917-W 11-25-70