

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-20,896-00-00

LEASE NAME Lund "A"

WELL NUMBER 1

660' Ft. from N Section Line

660' Ft. from W Section Line

SEC. 13 TWP. 3S RGE. 28 (E) or (W)

COUNTY Decatur

Date Well Completed 2-29-96

Plugging Commenced 2-29-96

Plugging Completed 2-29-96

#4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pickrell Drilling Co. Inc.

ADDRESS 110 N. Market, Suite 205 - Wichita, Kansas 67202

PHONE# (316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-23-96 (date)

by Don Butcher (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation N/A Depth to Top _____ Bottom _____ T.D. 4000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Casing			8 5/8"	225'KB	

RECEIVED
KANSAS CORP COM
03-12-1996
PDB MAR 12 A 11:53

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
P&A as follows: 25sx @ 2450', 100sx @ 1665', 40sx @ 275', 10sx @ 40', 15sx in rathole (total 190sx) of 60-40 poz, 6% gel w/1/4# floseal per sx. Complete @ 9:45 PM on 2-29-96.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Company Tools License No. 5123

Address 110 N. Market, Suite 205 - Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


C.W. Sebitts, President of Pickrell Drilling Company, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C.W. Sebitts

(Address) C. W. Sebitts, President
110 N. Market, Suite 205

Wichita, Kansas 67202
day of March, 19 96

SUBSCRIBED AND SWORN TO before me this 11th



Verdella Lewis
Notary Public

My Commission Expires: 6-06-98

ORIGINAL

PICKRELL DRILLING COMPANY, INC.

110 NORTH MARKET - SUITE 205
WICHITA, KANSAS 67202-1996
(316) 262-8427

#1 Lund "A"
C NW NW
Section 13-3S-28W
Decatur County, Kansas

CONFIDENTIAL

API#: 15-039-20,896 -00-00
660' From North Line of Section
660' From West Line of Section
ELEV: 2716' KB, 2715' DF, 2711' GL

- 2-22-96: MIRT.
- 2-23-96: (On 2-22) Spud @ 4:30 PM. Ran 5 jts. of new 8 5/8" 20# Csg. (tally 218.67) set @ 225'KB, cmt w/145sx of 60-40 poz, 2% gel, 3% CC. Cmt circ. PD @ 8:45 PM on 2-22-96. (On 2-23) Drlg. @ 330'.
- 2-26-96: (On 2-24) Drlg. @ 2057'. (On 2-25) Drlg. @ 3130'. (On 2-26) Drlg. @ 3743'.
- 2-27-96: Circ. @ 3830'. DST #1 3788-3812', 30"-60"-30"-30" Rec: 10' M (1% Oil), ISIP 20#, IFP 20-20#, FFP 20-20#, FSIP 20#.
- 2-28-96: Testing @ 3930'. (On 2-27) DST #2 3786-3868, 30"-60"-90"-90" Rec: 300' OCM (40% O, 60% M), 60' SOCWM (1% O, 50% M, 49% W), 180' SW (Chl 58,000 PPM), 540' total fluid. ISIP 1187#, IFP 50-71#, FFP 121-254#, FSIP 1147#. DST #3 3864-3930'.
- 2-29-96: RTD 4000'. DST #3 3864-3930', 30"-60"-30"-30" Rec: 10' M, IFP 20-20#, ISIP 40#, FFP 20-20#, FSIP 20#. Prep to run E-Logs.
- 3-01-96: (On 2-29) LTD 3995'. P&A as follows: 25sx @ 2450', 100sx @ 1665', 40sx @ 275', 10sx @ 40', 15sx in RH (total 190sx) of 60-40 poz, 6% gel w/1/4# FS/sx. Complete @ 9:45 PM on 2-29-96.

RELEASED

JUL 31 1997

FROM CONFIDENTIAL

MAR 1 1997
CONFIDENTIAL

RECEIVED
KANSAS CORP COMM
1997 MAR 12 A 11:53

SAMPLE TOPS

Anhydrite	2433 (+283)
Base/Anhydrite	2467 (+249)
Heebner	3733 (-1017)
Lansing	3774 (-1058)
Stark	3925 (-1209)
Base/Kansas City	3972 (-1256)
RTD	4000'

ELECTRIC LOG TOPS

Base/Fort Hays	987 (+1729)
Anhydrite	2432 (+284)
Heebner	3731 (-1015)
Lansing	3772 (-1056)
Stark	3930 (-1214)
Base/Kansas City	3973 (-1257)
LTD	3995'