

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-20,808 ~~00-00~~

LEASE NAME Chaffin

WELL NUMBER 1-20

2310 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 20 TWP. 3 RGE. 28 ~~XXX~~ (W)

COUNTY Decatur

Date Well Completed 3-6-87

Plugging Commenced 3-6-87

Plugging Completed 3-6-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Boundry Petroleum, Inc.

ADDRESS 350 Interlocken Pkwy, #250, Broomfield, CO 80020

PHONE# (303) 460-1550 OPERATORS LICENSE NO. 3271

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #6

Is ACO-1 filed? no If not, is well log attached? no

Sent to operator for completion

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	265	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump heavy mud to 2450'-2350', 25 sacks; pump heavy mud to 1650'-1250', 100 sacks and 1 sack floccel; pump heavy mud to 300'-140', 40 sacks; pump heavy mud 40' to solid bridge, 10 sacks; 15 sacks in the rathole; all cement 60/40 posmix, 6% gel, 3% ca. cl.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422


Address 801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton, Secretary/Treasurer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) Jack K. Wharton
801 Union Center, Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 10th day of March, 19 87

Clarice M. Mize
Clarice M. Mize Notary Public

Commission Expires: November 28, 1988

MAR 11 1987

03-11-1987