

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Decatur County. Sec. 9 Twp. 3S Rge. 28W ~~(XXXXXXXXXX)~~

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C NW SW

Lease Owner Rains & Williamson Oil Co.

Lease Name Bremer Well No. 1

Office Address 412 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 7/20/62 19__

Application for plugging filed 7/20/62 19__

Application for plugging approved 7/20/62 19__

Plugging commenced 7/20/62 19__

Plugging completed 7/20/62 19__

Reason for abandonment of well or producing formation no oil or gas found in commercial quantities

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4258 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	205'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

set plug at 550' and cement through drill pipe with 20 sacks cement. set plug at 180' and cement through drill pipe with 20 sacks. set plug at 35' and cap with 10 sacks cement.

07-30-1962
JUL 30 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 412 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains Partner (employee or owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains
412 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of July, 1962

My commission expires JANET JOHNSON
My commission expires Jan. 25, 1965

Janet Johnson
Janet Johnson Notary Public.



K
ROTARY DRILLING LOG

15-039 - 00187-00-00

Operator: Rains & Williamson Oil Co.
No. 1 Bremer, C NW SW, Sec. 9-3S-28W, Decatur County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.
 COMMENCED: 7/12/62
 COMPLETED: 7/20/62

REMARKS:
 set 204° of 8' 5/8" with 125 sacks

FORMATIONS:

Surface Soil and Sand	35°
Shale	1345°
Shale and Sand	1870°
Shale & Lime	2215°
Lime	2390°
Shale & Lime	2385°
Shale	2785°
Shale & Lime Shells	2985°
Shale & Lime Streaks	3145°
Lime & Shale	3265°
Shale & Shells	3400°
Shale & Lime Shells	3550°
Lime and Shale	3672°
Lime	3684°
Lime	3740°
Sand	3861°
Shale	3885°
Shale - Lime	4005°
Shale	4110°
Shale	4181°
Arbuckle	4250°
4258 - Rotary Total Depth	

RECEIVED
 STATE CONSERVATION COMMISSION
 JUL 30 1962
 CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.



 Wilson Rains - Partner

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, County of Sedgwick, this 27th day of July, 1962.

My Commission Expires:

JANET JOHNSON

My commission expires Jan. 25, 1965



 Janet Johnson Notary Public