


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Decatur County. Sec. 8 Twp. 3S Rge. 28 (E) (W) X
Location as "NE/CNW $\frac{1}{2}$ /SW $\frac{1}{2}$ " or footage from lines NW NW
Lease Owner Empire Drilling Company
Lease Name Zodrow Well No. 1
Office Address 650-4th National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 21, 1961 19
Application for plugging filed February 21, 1961 19
Application for plugging approved February 21, 1961 19
Plugging commenced February 21, 1961 19
Plugging completed February 21, 1961 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3875 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Sand-Shale	0	191	8 5/8"	178'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 400' with 20 sacks cement
Plug set at 175' with 20 sacks cement
Plug set at 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1961
02-28-1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld (employer of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
650-4th Nat'l. Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of February, 19 61

My commission expires October 21, 1962

[Signature]
Lucille H. Harr
Notary Public.

LOG

COMPANY: Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Zodrow # 1
 LOCATION: NW NW Section 8-3S-28W, Decatur County, Kansas
 COMMENCED: February 14, 1961
 COMPLETED: February 21, 1961
 ELEVATION: 2661 KB
 POTENTIAL: D & A

0	to	191	Sand-Shale
191	to	475	Shale
475	to	2353	Shale-Shells
2353	to	2385	Anhydrite
2385	to	2596	Shale-Shells
2596	to	2840	Shale-Lime
2840	to	2980	Shale-Shells
2980	to	3240	Shale-Lime
3240	to	3670	Lime-Shale
3670	to	3725	Lime
3725	to	3785	Lime-Shale
3785	to	3875	Lime
3875			Rotary Total Depth

SET: 178" 8 5/8" casing with 115 sacks cement.


ELECTRIC LOG TOPS:

Topeka	3507	- 846
Heebner	3621	- 960
Toronto	3653	- 992
Lansing	3661	-1000
Base Kansas City	3862	-1201
Schlumberger TD	3874	

RECEIVED
 STATE CORPORATION COMMISSION
 02-28-1961
 FEB 28 1961
 CONSERVATION DIVISION
 Wichita, Kansas

CERTIFICATION

I, Dan Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Zodrow # 1, NW NW Section 8-3S-28W, Decatur County, Kansas, as reflected by the files of Empire Drilling Company.


 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public within and for Sedgwick County, Kansas, this 27th day of February, 1961.


 Lucille H. Harr, Notary Public

My commission expires October 21, 1962.