

6 070546

MAR 6 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 029-20, 808-00-00

NW-NE-SW, SEC. 20, T. 2 S, R. 28 WE

2310 feet from (S) section line

3630 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3271

Lease Name Chaffin Well # 1-20

Operator: Boundary Petroleum Inc.

County Decatur 129.35

Name & Address 350 Interlaken Parkway

Well Total Depth 3980 feet

#250 Broomfield, Colorado

Conductor Pipe: Size 0 feet

Dave Armstrong 80020

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Tag # 179

Plugging Contractor Abercrombie Drilling Inc License Number 5422

Address Wichita, Kansas 67202

Company to plug at: Hour: 1:00 PM Day: 6th Month: March Year: 19 87

Plugging proposal received from Harold Maloy

(company name) Abercrombie Drilling Inc (phone) 303-460-1550

were: 8 5/8" 265 FT SR. cmt. 1/175 SK 60/40 Poz. gel, ca. cl., 2% 3% By Halliburton

Elv 2712, Amby 2431, Mud Condition 9.1 Weight, 49 Vis, 91 water loss.

Proposed - 190 SK 60/40 Pozmix gel, ca. cl., 1/2 cmt. (No Circ. Problems)

Spot with Drill Stem, Recondition hole, slurry mud between all plugs

25 SK @ 2450, 100 SK @ 1650, 40 SK @ 300, 10 SK @ 40, 15 SK Rat

circulate, Plugging Proposal Received by Marion Schmidt (TECHNICIAN)

Plugging Operations attended by Agent: All Part None

Operations Completed: Hour: 2:00 PM Day: 6th Month: March Year: 19 87

ACTUAL PLUGGING REPORT Ordered 190 SK 60/40 Pozmix gel, ca. cl., 1 cmt. 5/8" Plug.

Spotted with Drill Stem, Reconditioned hole, slurry mud between plug

1st. Plug @ 2450' 1/25 SK cmt, 2nd Plug @ 1650 FT 1/100 SK

cement 1/4 SK cello mixed in, 3rd Plug @ 300 FT 1/40 SK cmt.

4th Plug 1/2 SK Nulls + Plug 1/10 SK cement, 15 SK Rat Hole (circulate)

Cemented by Halliburton Cem. Co

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-23-87 Rec'd 3-11-87

INV. NO. 16386

Signed Marion Schmidt (TECHNICIAN)