

7-18

6 070702

API NUMBER 15- 039-20,831-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE, SEC. 6, T 3 S, R 28 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 6033

3630 feet from S section line

800 feet from E section line

Operator: Murfin Drilling Co.
Name & Address: 250 North Water #300
Wichita, Ks. 67202
Todd Aikins

Lease Name Kolsky Well # 1-6

County Decatur

Well Total Depth 3875 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Tag No. 608 License Number 6033
Address 250 Nr Water #300 Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 18 Month: July Year: 19 88

Plugging proposal received from Rodney Farr
(company name) Murfin Drilling (phone) _____

were: 8 5/8" - 347' S.P. cwc w/210 sks cement. 60/40 Poz 3% Gel 2% Ca Cl (By Halliburton)
Elv. 2627'. Anhy 2311' No Arbuckle. Mud condition 50 vis. 9.4 weight; 10. water loss.

No circulation problems. Spot with drill stem mud between all plugs. Proposal 225 sks
60/40 Poz 6% Gel 2% Ca Cl and 8 5/8" plug. 25 sks at 2325'; 100 sks w/1 F.C. at 1570';
50 sks at 390'; 10 sks at 40'; 15 sks rathole (Cir) 10 sks mousehole (Cir)

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:30AM Day: 18 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Ordered 225 sks 60/40 Poz 6% Gel 2% Ca Cl and 8 5/8" plug.
Spot with drill stem, circulate, mud between all plugs. 1st plug at 2325' w/25 sks cement.
2nd plug at 1570' w/100 sks w/1 sks F.C. 3rd plug at 390' w/50 sks cement. 4th plug Hulls
Plug 40 w/10 sks cement; 15 sks in rathole (cir) 10 sks in mousehole (cir)

Remarks: Cemented by Halliburton Cement
(If additional description is necessary, use BACK of this form.)

INVOICED did not serve this plugging.

DATE 10-25-88

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt

INV. NO. 22703