

6 070368

API NUMBER 15- 039- 20, 768-00-00 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C-SE-NW, SEC. 4, T 3 S, R 28 W

3190 feet from S section line

3190 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5816

Lease Name KOERPERICH Well # 1

Operator: FALCON EXPLORATION, INC.
Name & Address: 1531 HSB. BLDG. 125^N
WICHITA, KANS.
67202

County DECATOR 124.15

Well Total Depth 3820 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated TAG # 603

Plugging Contractor MURFIN DRILLING Co. License Number 6023

Address 250 North WATER, WICHITA, KANS. 67202 #200

Company to plug at: Hour: 3:00 AM Day: 11th Month: JULY Year: 19 85

Plugging proposal received from LARRY WAGONER

(company name) MURFIN DRILLING Co. (phone) 316-262-1278

were: 8 5/8" - 260 EI SP. CUM 195 SK 60/40 Pozmix 3% Ca-Cl. BY HALLIBURTON

ORDER 200 SK 60/40 Pozmix 6% 3% SK CELLO FLAME AND 8 5/8" PLUG.

SPOT WITH DRILL STEM, RECONDITION HOLE (VISCOSITY) HEAVY MUD BETWEEN ALL PLUGS.

NO ARBUCKLE, KC. WELL, NO CIRCULATION PROBLEMS, MUD CONDUCTION

9.2 WEIGHT, 50 VISCOSITY, 12 WATER LOSS, ELV. 2665', ANHY. 2368'

Plugging Proposal Received by Marion J. Smith
DOIC (TECHNICIAN)

Plugging Operations attended by Agent? All _____ Part _____ None

Operations Completed: Hour: 4:00 AM Day: 11th Month: JULY Year: 19 85

ACTUAL PLUGGING REPORT ORDERED 200 SK 60/40 Pozmix 6% 3% SK CELLO FLAME 8 5/8" PLUG

SPOTTED WITH DRILL STEM, RECONDITIONED HOLE, HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 2370 EI w/ 30 SK CNT, 2nd PLUG @ 1610 EI w/ 100 CNT, 1 SK CELLO FLAME.

3rd PLUG @ 270 EI w/ 50 SK CNT, 4th PLUG ^{SOLID BRIDGE} HULLS-PLUG @ 40 EI w/ 10 CNT.

10 SK IN RAT HOLE, (CIRCULATE)

CEMENTED BY HALLIBURTON CNT

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED RECEIVED
STATE CORPORATION COMMISSION

DATE 7-26-85 07-19-1985

INV. NO. 9125
7-11 AUG 14 1985

Signed Marion J. Smith
DOIC (TECHNICIAN) 10
7-18-85
mgs.