

6 030462

API NUMBER 15-039-20,759-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NWNE SEC. 17, T. 3 S., R. 28

4950 feet from (S) section line

990 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name RUZICKA Well # 1

Operator: FALCON EXPLORATION INC.

County DECATUR 127.57

Name & Address 1531 KSB BLDG.

Well Total Depth 3925 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 7/8 feet

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON SERVICES License Number _____

Address OBERLIN KANSAS

Company to plug at: Hour: PM Day: 30 Month: 5 Year: 19 85

Plugging proposal received from ZACK LEWIS

(company name) FALCON EXP. (phone) _____

were: 8 7/8 SET @ NA 4 1/2 SET @ NA ORDER COM. CEMENT AND SAND PLUG BOTTOM SHOOT OFF AND STRIP 4 1/2" CASING ORDER 180 SX. 50# 40026 GEL 3% CC 40 SX. GEL 4 SX. HULLS HALLIBURTON CEMENT CO. LARUE WATER TRUCKS

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 PM Day: 30 Month: 5 Year: 19 85

ACTUAL PLUGGING REPORT WITH BAILER 4 SX. COM. CEM. ON BOTTOM SAND 50' ABOVE PERFS

4 SX. COM. CEM. W/ BAILER ON SAND SHOOT OFF STRIPPED 1765' CASING.

PUMP DOWN 8 7/8 W/ 4 SX. HULLS + 20 SX. GEL, 100 SX. CEM. MIX., 20 SX. GEL.

8 7/8 W. P., 80 SX. CEM. MIX. MAX. PSI. 500* CLOSE IN 150"

RECEIVED
STATE CORPORATION COMMISSION

Remarks: _____ JUN 07 1985 6-7-85

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodnow
(TECHNICIAN)

DATE 6-12-85

INV. NO. 8458 5.30 JUL 12 1985