

6030448

15-039-30064-00-01

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- _____

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

990 feet from W(S) section line

1030 feet from W(E) section line

Operator: Halliburton Oil Producing Co.
Name & Address: 2915 Classen Blvd.
Oklahoma City, Ok.
73106

Lease Name Witt Well # 3

County Decatur 127.73

Well Total Depth 3930 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 259'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well KCC of B D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 14 Month: 5 Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone) _____

were: 8 7/8 set @ 259' w/ 175 st. 4 1/2 set @ 3928 w/ 175 st. Perf 3805' - 3893'

PBTD 3896' Order 8 1/2" Com. Con. Sand. Plug Bottom and shoot off pipe and

recover. Order Top plug - 180 st 50/50 psg 6 bag 3% cc 40 st gel 4 st hulls

8 7/8 W.P. Halliburton Cement Co. have water truck.

Recovered 1500' 4 shots @ 2500' 2000' 1800' 1500'

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:PM Day: 14 Month: 5 Year: 19 85

ACTUAL PLUGGING REPORT Bottom Plug. With bailer 4 st on CIBP sand to 3750

4 st Com. Con. - Top Plug - pump down 8 7/8 w/ 4 st hulls 19 st gel 100 st

Com. mix. 21 st gel 8 7/8 W.P. 80 st Com. mix. Max 200# shut in 200#

Plug Complete.

RECEIVED
STATE CORPORATION COMMISSION
6-5-85
JUN 05 1985

Remarks: _____
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED (do not observe this plugging.)

DATE 6-7-85

Signed Carl Goodrow
(TECHNICIAN)

4
5-31-85
MMP

INV. NO. 8425