

X

4-070085

12-13

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-039-20,906-00-00

C NW SW /4 SEC. 13, 03 S, 28 W  
1980 feet from S section line  
4620 feet from E section line

Operator license# 5123

Lease: Lund "B" Well # 1

Operator: Pickrell Drilling Company

County: Decatur 130.00

Address: 110 N. Market - #205  
Wichita, Kansas 67202

Well total depth 4000 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 229 feet

ABAND. oil well, Gas well, Input well, SWD., D&A X

Plugging contractor: Pickrell Drilling Company License# 5123

Address: 110 N. Market - #205 - Wichita, Kansas 67202

Company to plug at: Hour: 11:00 A.M. Day: 13 Month: December Year: 1997

Plugging proposal received from: Mike Kern

Company: Pickrell Drilling Company Phone: 316-262-8427

Were: Ordered 190 sxs 60/40 pozmix - 6% gel - 1/4# flo seal per sack - one 8 5/8 W.P.  
Spot plug through drill pipe with heavy drilling mud between all plugs.  
8 5/8" set at 229'.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 2:30 P.M., Day: 13, Month: December, Year: 1997

Actual plugging report: No ar buckle cut.

1st. Plug at 2445' w/25 sxs. - Anhydrite 2429' - 2462'.

2nd. Plug at 1580' w/100 sxs. - Dakota Base.

3rd. Plug at 279' w/40 sxs. - Bottom of surface pipe +50'.

4th. Plug at 40' w/10 sxs with 8 5/8" wiper plug.

15 sxs in rathole.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING X, CASING Elevation: 2720 GL

I did [ ] / did not [ X ] observe the plugging.

Richard Williams  
(agent)

Form CP-2/3

INVOICED

DATE 1-23-98

INV. NO. 49980

RECEIVED  
MMS&S  
JAN 22 0 P. 1998  
01-22-1998

①