

4-050227

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-039-20,896-00-00

2-29

C NW NW /4 SEC. 13, 03 S, 28 W  
~~660~~ 4620 feet from S section line  
~~660~~ 4620 feet from E section line

Operator license# 5123

Lease: Lund Well # A-1

Operator: Pickrell Drilling Company, Inc.

County: Decatur

Address: 110 N. Market - Suite #205  
Wichita, Kansas 67202  
316-262-8427

Well total depth 4000 <sup>130.00</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 225 feet

Aband. oil well, Gas well, Input well, SWD, D & A

Plugging contractor: License# -

Address:

Company to plug at: Hour: P.M. Day: 29 Month: February Year: 1996

Plugging proposal received from:

Company: Phone:

Were: Order 190 sxs 60/40 pozmix - 6% gel - 1/4# Flo-seal per sack

RECEIVED  
KANSAS CORPORATION COMMISSION  
03-08-1996  
MAR 08 1996

Plugging Proposal Received by: Marvin Miller

CONSERVATION DIVISION  
WICHITA, KS

Plugging operations attended by agent? All [ ], Part [ ], None [  ]

Completed: Hour 9:45 P.M., Day: 29, Month: February, Year: 1996

Actual plugging report:

- 1st. Plug at 2450' with 25 sxs cement.
- 2nd. Plug at 1665' with 100 sxs cement.
- 3rd. Plug at 275' with 40 sxs cement.
- 4th. Plug at 40' with 10 sxs cement - 8 5/8" wiper plug.
- 15 sxs cement in rathole.

Remarks:

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES  NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

I did [ ] / did not [  ] observe the plugging.

INVOICED

Marvin Miller  
(agent)

Form CP-2/3

DATE MAR 11 1996

INV. NO. 45021

2-29