



15-039-20225-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Art Hunt of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Hunt guarantees payment of the plugging fee.

Operator's full Name: Jeff C. Lyle

Complete Address: 816 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Clark Well No. 1

Location: NE-SW Sec. 10 Twp. 3 Rge. (E)(W) 28

County: Decatur Total Depth 3935' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hunt was instructed to plug the well as follows:

206'--8 5/8" Surface casing, cement circulated with ???.
Top of Dakota section @ 1275'.

Circulate hole with heavy mud. Pull DP to 1500' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Dehls
Conservation Division Agent