



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-039 - 20175-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
09-15-1970
SEP 15 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Bryan Well No. A-1

Location: SE-SW-NE Sec. 7 Twp. 3 Rge. (E)(W) 28

County: Decatur Total Depth 3685' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

285'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1225'.

Circulate hole with heavy mud, pull DP to 1375' and displace 100 Sx. cement
thru DP. PULL DP to 325' and displace 25 Sx. cement thru DP. Pull DP, set
bridge @ 40' with 1/2 sack hulls and 10 Sx, cement to bottom of cellar.

Very truly yours,

Conservation Division Agent