



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-039-20062-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 25 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Chas. Keevert of Birmingham-Bartlett Drlg. Co., has this date requested permission to plug the following described well:

Mr. Keevert guarantees payment of the plugging fee.

Operator's full Name: Birmingham-Bartlett Drilling Company,

Complete Address: 300 Kaufman Building, Wichita, Kansas.

Lease Name: Unger Well No. C-2

Location: N/2-NE-NE Sec. 18 Twp. 3 Rge. (E)(W) 28

County: Decatur Total Depth 3910' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Keevert was instructed to plug the well as follows:

329'--8 5/8" Surface casing, cement circulated with 210 Sx.
3910'--4 1/2" Production casing cemented on bottom with 150 Sx. No Plug back.
Top perforations @ 3750'.

Push plug to 3700', build sand bridge and set 3 Sx. cement with dump bailer.
Squeeze hole with 30 sacks gel, 5 sacks hulls and 130 Sx. cement staged.

Very truly yours,


 Conservation Division Agent