

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-029-2011-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 25 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Rowe of Slawson Drlg. has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 one twenty bldg., Wichita, Ks.

Lease Name: Steinmetz "A" Well No. 1

Location: 150' N of G NW NE Sec. 5 Twp. 3 Rge. (E)(W) 28

County: Decatur Total Depth 3607' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Rowe was instructed to plug the well as follows:
 Gun pits, circulate heavy mud, set cementing plug at 1700' and displace
 100 sk cmt thru drill pipe. Heavy mud to 250' set cementing plug and
 displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
 plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Muesey
 Conservation Division Agent