



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
05-09-1968  
MAY 9 1968  
CONSERVATION DIVISION  
Wichita, Kansas

15-039-20043-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Champlin Petro. Co. & Rains & Williamson Oil Co. Inc.,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Rhomine Smith Well No. 1

Location: CSW-SW Sec. 1 Twp. 3 Rge. (E)(W)28

County: Decatur Total Depth 3970' Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Walker was instructed to plug the well as follows:

242'--8 5/8" Surface pipe, cement circulated with 160 Sx.  
Top of Dakota section @ 1200'.

Circulate hole with heavy mud. Pull DP to 1435' and displace 100 Sx.  
cement thru DP. Pull DP to 270' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. A. Nichols  
Conservation Division Agent