



15-039-20224-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 10 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of A. L. Abercrombie, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Bremer Well No. 1

Location: CSW-NW Sec. 16 Twp. 3 Rge. (E)(W) 28

County: Decatur Total Depth 3954' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

223'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1350'.

Circulate hole with heavy mud. Pull DP to 1575' and displace 75 Cu. Ft. cement thru DP. Pull DP to 245' and displace 25 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent