

15-039-20225-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

*[Handwritten mark]*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
02-10-1972  
FEB 10 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Jeff C. Lyle,

Complete Address 816 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Clark Well No. 1

Location NE-SW Sec. 10 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 3935'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Rains & Williamson Oil Company, Incorporated,

Address 1425 Wichita Plaza, Wichita, Kans. License No.       

Operation Completed: Hour 6:15 AM Day 3 Month 2 Year 1972

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 110 Cu. Ft. cement  
thru DP from 1500' to 1175'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 2/11/72  
INV. NO: 5155-W

Signed: A. L. [Signature]  
Well Plugging Supervisor