

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
09-15-1970  
SEP 15 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20175-00-00

Operator's Full Name Donald C. Slawson,  
Complete Address 408 One-Twenty Building, Wichita, Kansas.  
Lease Name Bryan Well No. A-1  
Location SE-SW-NE Sec. 7 Twp. 3 Rge. (E) (W) 28  
County Decatur Total Depth 3685'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Slawson Drilling Company, Incorporated,  
Address 408 One-Twenty Building, Wichita, Kansas. License No.         
Operation Completed: Hour 6:00 PM Day 27 Month 8 Year 1970

The above well was plugged as follows:

285'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1225'.  
        
Circulated hole with heavy mud. Pulled DP to 1450' and displaced 100 Sx. cement thru  
DP from 1450' to to 1125'. Pulled DP to 300' and displaced 20 Sx. cement thru DP  
from 300' to 240'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement  
to bottom of cellar.  
        
      

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. J. Deibel*  
Well Plugging Supervisor

DATE 9/15/70  
INV. NO. 2534-W