

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

94  
-039-  
15-~~15~~20155-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1970  
CONSERVATION DIVISION  
Wichita, Kansas

*SLAWSON*

Operator's Full Name Donald C. Slawson, Incorporated,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Shaw Well No. B-1

Location APP C NE SE 660' W. & 2040' N of <sup>SEC</sup> GSE Sec. 7 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 3870'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Building, Wichita, Kansas. License No.       

Operation Completed: Hour 10:00 PM Day 25 Month 4 Year 1970

The above well was plugged as follows:

338'--8 5/8" Surface casing, cement circulated with 300 Sx.  
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 100 Sx. cement thru  
DP from 1500' to 1175'. Pulled DP to 370' and displaced 25 Sx. cement thru DP from  
370' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Dickols*  
Well Plugging Supervisor

DATE 4/28/70  
INV. NO. 1809-W