

44
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-039-00188-00-00

DEC 17 1962
12-17-1962
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Birmingham & Bartlett

Complete Address: 300 Kaufman Bldg Wichita, Kans

Lease Name Morrison Well No. 1

Location CSW SW Sec. 8 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 3900

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Plugging Contractor: same

Address: License No.

Operation Completed: Hour 3;30PM Day 14 Month 12 Year 62

The Above well was plugged as follows:

8 5/8" 272' circulated with cement.

Circulated hole with heavy mud, set plug at 550', displaced 20 sax
cement through drill pipe, heavy mud to 240', displaced 20 sax
cement through drill pipe, heavy mud to 40', set plug, 1/2 sack
hulls and filled to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edward Petty*
Well Plugging Supervisor

DATE 12/19/62
INV. NO. 6238-W