

15-039-20224-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
01-10-1972
JAN 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name A. L. Abercrombie, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Bremer Well No. 1

Location CSW-NW Sec. 16 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 3954'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 10:00 AM Day 6 Month 1 Year 1972

The above well was plugged as follows:

223'--8 5/8" Surface casing, cement circulated with 150 Sx. (6 3/4" Hole).
Top of Dakota section @ 1350'.

Circulated hole with heavy mud. Pulled DP to 1575' and displaced 75 Cu. Ft. cement
thru DP from 1575' to 1275'. Pulled DP to 245' and displaced 25 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. L. Nichols
Well Plugging Supervisor

DATE 1-12-72

INV. NO. 4974-W