

KANSAS

4
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20211-00-00

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1971

CONSERVATION DIVISION
Wichita, Kansas

5-24-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Birmingham-Bartlett Drilling Company,

Complete Address 300 Kaufman Building, Wichita, Kansas.

Lease Name Ruzicka Well No. 1

Location SE-NW-NW Sec. 17 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 3906'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza Building, Wichita, Kansas License No.

Operation Completed: Hour 9:30 PM Day 20 Month 5 Year 1971

The above well was plugged as follows:

321'--8 5/8" Surface casing, cement circulated with 210 Sx.
Top of Dakota section @ 1350'.

Circulated hole with heavy mud. Pulled DP to 1575' and displaced 100 Sx. cement thru
DP from 1575' to 1250'. Pulled DP to 340' and displaced 25 Sx. cement thru DP from
340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 5-24-71

INV. NO. 3744-10