

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
09-17-1970  
SEP 17 1970  
CONSERVATION DIVISION  
Wichita, Kansas

15-039-20181-00-00

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Unger Well No. 1

Location CE/2-NW-NE Sec. 18 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 3410'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 1:45 AM Day 15 Month 9 Year 1970

The above well was plugged as follows:

300'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 1225'.

Circulated hole with heavy mud. Pulled DP to 1450' and displaced 100 Sx. cement thru  
DP from 1450' to 1125'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from  
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickels  
Well Plugging Supervisor

INVOICED

DATE 9-17-70

INV. NO. 2548-W