

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20062-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 25 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Birmingham-Bartlett Drilling Company,

Complete Address: 300 Kaufman Building, Wichita, Kansas.

Lease Name Unger Well No. G-2

Location N/2-NE-NE Sec. 18 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 3910'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 9

Operation Completed: Hour 1:30PM Day 20 Month 11 Year 1968

The Above well was plugged as follows:

329'--8 5/8" Surface casing, cement circulated with 210 Sx.  
3910'--4 1/2" Production casing cemented on bottom with 150 Sx. No plug back, Top per-  
forations @ 3750'.

Pushed plug to 3700', built sand bridge and set 3 Sx. cement with dump bailer. Pulled  
4 1/2" casing and squeezed well with initially 5 sacks hulls and 3 sacks gel and followed  
with 100 Sx. cement from 1525 to 1200' then 21 sacks gel from 1200' to 360' and followed  
with 20 Sx. cement from 360' to 300' then 6 sacks gel from 300' to 30' and finally 10  
Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-100#. Final shut-in  
pressure-50#. (Mudding and cementing operations performed by Halliburton Services).

I hereby certify that the above well was plugged as herein stated.

Signed: M. S. Nichols  
Well Plugging Supervisor

INVOICED

DATE 11/26/68  
INV. NO. 8869-w