

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-30000-00-00

RECEIVED
STATE CORPORATION COMMISSION

MAR 31 1985
03-31-1985
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name John O. Farmer, Incorporated,
Complete Address: 370 West Wichita, Russell, Kansas.
Lease Name Kirkendall Well No. 1
Location CSE-SW Sec. 14 Twp. 3 Rge. (E) (W) 28
County Decatur Total Depth 4000
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Above
Address: License No.

Operation Completed: Hour 3:30PM Day 26 Month 3 Year 1965

The Above well was plugged as follows:

224'--8 5/8" Surface pipe, cement circulated with 130 Sx.
Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.
cement thru DP. Heavy mud to 210', set plug with 1/2 sack hulls and dis-
placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls
and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dechak
Well Plugging Supervisor

DATE 3/31/65
INV. NO. 904-W