

4-032408

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-039-20,006 00-00

NW NE SE /4 SEC. 06, 03, 29 W
2310 feet from S section line
990 feet from E section line

Operator license# 4315 (Expired 04-30-1991)

Lease: Pollnow Well # 2

Operator: Formerly (Brazos Pet. Co.)
500 W. Wall Street
Address: P.O. Box 1782
Midland, Texas 79702
915-682-6644

3/31

County: Decatur
Well total depth 3970 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 232 feet

Fee waived

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: R.L. Hrbek License# 31274

Address: Rt. 1 - Box 11 - Merino, CO 80741

Company to plug at: Hour: A.M. Day: 31 Month: March Year: 2000

Plugging proposal received from: Carl Goodrow - KCC - R.L. Hrbek

Company: KCC and R.L. Hrbek Phone:

Were: Order 8 yards Redimix Concrete.
Order bottom plug and 5 sxs common cement.
Exempt Area.
The operator cannot be found and this lease is on the list for "Fee Fund".
The contractor agreed to plug out and clean up the lease for the equipment.
The landowner is in full agreement and very pleased.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:30 A.M., Day: 31 Month: March, Year: 2000

Actual plugging report: 8 5/8" set at 232' w/140 sxs cwc. 5 1/2" set at 3964' w/100 sxs.
Prod. Perfs 3780' - 3782'. Set plug at 3730' with 5 sxs common cement on plug with bailer.
Shot and recovered 1200' of 5 1/2". Load hole with 8 yards Redimix to surface. Plug complete.

Remarks:
Condition of casing (in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug (in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED
DATE 5/19/00
INV. NO. 61751

On May report

RECEIVED
STATE CORPORATION COMMISSION

Form CP-2/3

APR 28 2000

CONSERVATION DIVISION
Wichita, Kansas

(R)

15-039-20006-00-00

The operation has been gone for a long time. Mr. Hubek agreed to give wells for equipment. The wells were in the abandoned well files. District was happy to get rid of 5 abandoned wells, solve two complaints and recommend that no plugging assessment be levied against Mr. Hubek.

Herb Deaves
Dist Supervisor
4-27-2000.