

To: 6 031245  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

X 5-1015-039-00088-00-00  
API NUMBER 15- 1958 E-7653  
SW NE SE, SEC. 5, T. 3 S, R. 29 W/E  
1650 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5920

Operator: TEPE Oil and Gas Co.  
Name & Address: Box 522  
Canton, Ks. 67428

Lease Name Pollnow Unit Well # 7  
County Decatur 127.24  
Well Total Depth 3915 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well  SWD Well  U&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton License Number \_\_\_\_\_

Address Oberlin

Company to plug at: Hour: \_\_\_\_\_ AM Day: 10 Month: May Year: 19 89

Plugging proposal received from Terry Bandy

(company name) TEPE (phone) \_\_\_\_\_

were: 8 5/8" set at 211' w/175 sks. 4 1/2" set at 3834' w/125 sks. PBTD 3799'. D.V. at 2200'  
w/cement and Black Magic to surface. Perfs 3745' - 3749'. Order 170 sks HDL. 65/35 poz 10% gel  
2% dicel 400# Hulls. Halliburton Cement Company. LaRue Water Trucks.

RECEIVED  
STATE CORPORATION COMMISSION  
6-6-89

JUN 6 1989 Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations <sup>CONSERVATION DIVISION</sup> <sub>WICHITA, KANSAS</sub> by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 8:10AM Day: 10 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 4 1/2" w/150 sks cement blend w/400# Hulls mixed into ma  
psi 500#. Close in psi 200#. Squeezed backside w/20 sks cement blend to max psi 300#.

Close in 200# psi. Plug complete.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby authorize to observe this plugging.

DATE 6-8-89  
INV. NO. 25024  
JUL 11 1989  
5-10

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow