

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-039-20,015 -00-~~8d~~

SE SW NE /4 SEC. 06, 03, 29 W  
2970 feet from S section line  
1650 feet from E section line

Operator license# 4315 (Expired 04-30-1991)

Lease: Amanda Well # 2

Operator: Formerly (Brazos Pet. Co.)  
500 W. Wall Street  
Address: P.O. Box 1782  
Midland, Texas 79702  
915-682-6644

County: Decatur  
Well total depth 3980 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 228 feet

Fee waived

4/19

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: R.L. Hrbek License# 31274

Address: Rt. 1 - Box 11 - Merino, CO 80741

Company to plug at: Hour: A.M. Day: 19 Month: April Year: 2000

Plugging proposal received from: Carl Goodrow - KCC - R.L. Hrbek

Company: KCC and R.L. Hrbek Phone: -

Were: Order 12 yards Redimix Concrete.  
Order bottom plug and 5 sxs common cement.  
Exempt Area.  
The operator cannot be found and this lease is on the list for "Fee Fund".  
The contractor agreed to plug out and clean up the lease for the equipment.  
The landowner is in full agreement and very pleased.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 12:00 P.M., Day: 19 Month: April, Year: 2000

Actual plugging report: 8 5/8" set at 228' w/150 sxs cwc. 5 1/2" set at 3953' w/100 sxs.  
Prod. Perfs 3796' - 3800'. Squeezed at 2980' to 3009' and from 2200'. Anquard from surface  
down. Set plug at 3740' with 5 sxs common cement on plug with bailer.  
Shot & recovered 1100' of 5 1/2" casing. Filled hole with 8 yards Redimix cement to surface.  
Plug complete.

Remarks:  
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

RECEIVED  
STATE CORPORATION COMMISSION

Form CP-2/3

APR 28 2000

CONSERVATION DIVISION  
Wichita, Kansas



INVOICED

DATE 5/19/00

AMOUNT 60751

On May report