

4-032393

15-039-20011-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1967

NW SW SW /4 SEC. 05, 03, 29 W
990 feet from S section line
4950 feet from E section line

Operator license# 31274

11-12

Lease: Viola Schultz Well # 2

Operator: R.L. Hrbek

County: Decatur 123.34

Address: Rt. 1 - Box 11
Merino, CO 80741

Well total depth 3795 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 217 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: R.L.Hrbek License# 31274

Address: Rt. 1 - Box 11 - Merino Co 80741

Company to plug at: Hour: P.M. Day: 12 Month: November Year: 1999

Plugging proposal received from: R.L.Hrbek

Company: R.L.Hrbek Phone: _____

Were: Order Redimix to fill wellbore.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 4:00 P.M, Day: 12 Month: November, Year: 1999

Actual plugging report: 8 5/8" set at 217' w/150 sxs 5 1/2" set at 3793' w/150 sxs.
Prod. Perfs 3766' - 3770'. PBD 3788'. Casing squeezed at 2251' with 400 sxs. Set bridge
plug at 3700' with 5 sxs common cement on plug with bailer. Shot off and recovered 1200' of
5 1/2" casing. Loaded casing with Redi-Mix - pulled casing. Filled hole with total of 8 yards
Redi-Mix. Pulled casing - topped off with 4 yards Redi-Mix. Used total 12 yards.
Fluid Level 2500'. Plug complete.

Remarks: _____

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____

Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES NO _____

Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did / did not observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE 12/3

INV NO. 60907

RECEIVED
STATE CORPORATION COMMISSION Form CP-2/3

NOV 24 1999
CONSERVATION DIVISION
Wichita Kansas

2