

4-031680

4-15
13-039-00548-00-00

17
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1958

C NW SE /4 SEC. 04, 03 S, 29 W
1980 feet from S section line
1980 feet from E section line

Operator license# 5920

Lease Polnow well # 6

Operator: Te-Pe Oil & Gas Company

County Decatur

Address: P.O. Box 522
Canton, Kansas 67428

Well total depth 3925 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 225 feet

127.56

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton License# -

Address: Oberlin, Kansas

Company to plug at: Hour: A.M. Day: 15 Month: April Year: 92

Plugging proposal received from: Terry Bandy

Company: Te-Pe Oil & Gas Company Phone:

Were: Order 350 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Rods and tubing pulled with hole open to produce perf's.
Back side squeezed @ 2657' w/550 sx.
D.V. 2163' with cwc. with 175 bbl. black magic.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:45A.M., Day: 15, Month: April, Year: 92

Actual plugging report: 8 5/8" set @ 225' w/175 sx. 4 1/2" set @ 3988'
w/125 sx. Perf. @ 3733'. P.B.T.D. 3865'. Squeezed 4 1/2" w/295 sx.
cement blend w/500# hulls mixed in to Max. P.S.I. 700#. Close in @ 700#.
8 5/8" squeeze w/10 sx. to 500#. Close in 300#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Any plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation:

I did X / did not observe the plugging.

DATE 5-18-92

INV. NO. 35-261

Carl Goodrow

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1992
CONSERVATION DIVISION
Wichita, Kansas

5-11-92