

X 5-10 15-039-19034-00 ~~00~~ *ad*

6 031246

API NUMBER 15- 1960 E-7653

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C W/2 SE, SEC. 3, T 3 S, R 29 W/E  
1320 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5920

Lease Name Pollnow Unit Well # 17

Operator: TEPE Oil and Gas Company  
Name & Address: Box 522  
Canton, Ks. 67428

County Decatur 123.27  
Well Total Depth 3793 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 205

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well  SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton License Number \_\_\_\_\_

Address Oberlin, Ks.

Company to plug at: Hour: AM Day: 10 Month: May Year: 19 89

Plugging proposal received from Terry Bandy

(company name) TEPE (phone) \_\_\_\_\_

were: 8 5/8" set at 205' w/175 sks. 5 1/2" set at 3761' w/100 sks. PBTD 3736'. Perfs  
3692' - 95'. Perf at 1400' w/100 sks. Order 145 sks. HDL 65/35 Poz 10% Gel  
2% Dixel 350# Hulls. Halliburton Cement Co. Larue Water Trucks.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 6 1989 6-6-89

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:40AM Day: 10 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/120 sks cement blend w/350# Hulls  
mixed into max psi 1000#. Close in psi 500#. Squeeze backside w/25 sks cement  
blend to max psi 300#. Close in 150#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

INVOICED

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow

DATE 6-8-89

INV. NO. 25025

JUL 1 1 1989