

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-19002-00-00
Spot: CW2SW Sec/Twnshp/Rge: 3-3S-29W
1320 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: POLLNOW UNIT Well Number: 15
County: DECATUR Total Vertical Depth: 3753 feet

Operator License No.: 31274
Op Name: HRBEK, R.L.
Address: RR 1, BOX 11
MERINO, CO 80741

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 197
Production: Size 5.5 feet: 3752
Liner: Size feet:

3121.97

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/06/2001 4:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: R. L. HRBEK Company: NORTHWEST WELL SERVICE, INC. Phone: (303) 522-4115

Proposed
Plugging
Method:

Order 8 yards Redi-Mix - 5 sxs common cement - 3000# sand with 40 gallons water per yard.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/06/2001 5:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 197' cwc. 5 1/2" set at 3752' w/175 sxs.
Prod. Perfs 3703' - 3707'.
Exempt area. Fluid level 3500'.
Filled 5 1/2" and 8 5/8" with 8 yards Redi-Mix (12 yards by yield).
Plug complete.

RECEIVED

AUG 28 2001

KCC WICHITA

Remarks: LEASE ALSO KNOWN AS NITSCH #2.

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

INVOICED

Form CP-2/3

AUG 23 2001

DATE

8-29-01

INV. NO.

2002060303

Renamed → Pollnow #15

ANDERSON-PRICHARD #2 NITSCH 3-3-29W
C W2 SW

Contr. PEEL BROS DECATUR County

E 267 1/4 RB Comm. Comp. 6-24-60 IP 52 BOPD

Tops	Depth	Datum
TOP	3171	-800
HEEB	3639	-965
TOR	3668	-991
LANS	3682	-1008
POLLNOW ZN	3701	-1030
TD	3753	-1079

Casing

8" 197

5" 3752

DST 3700-13/1 HR, 60' H OCM,
560' FR 0, BHP 670-600#/30
CO 3724: PERF 16/3703-07: FU
30' OCM/30": PMP 36 BOPH
NW

POLLNOW POOL:

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS