

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21890-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 23-28S-8W
990 feet from N Section Line, 2310 feet from E Section Line
Lease Name: PRAY Well #: 3
County: KINGMAN Total Vertical Depth: 4500 feet

Operator License No.: 5254
Op Name: MIDCO EXPLORATION, INC.
Address: 414 PLAZA DRIVE #204
WESTMONT, IL 60559

PROD Size: 4.5 feet: 4242
SURF Size: 8.625 feet: 280

146²⁵

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/12/2004 4:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: DAVID MAYFIELD Company: MIDCOEXPLORATION, INC. Phone: (620) 786-9166

Proposed Plugging Method: Place C.I.B.P. @ 4,050' & top with 2 sxs. cement. Shoot casing off. Pull casing to 1,175' & spot 35 sxs. cement. Pull casing to 750' & spot 35 sxs. cement. Pull casing to 330' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: NONE
Date/Time Plugging Completed: 07/12/2004 6:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Placed C.I.B.P. @ 4,053' & topped with 2 sxs. cement. Shot casing off @ 2,146'. Pulled casing to 1,182' & spotted 35 sxs. cement. Pulled casing to 760' & spotted 35 sxs. cement. Pulled casing to 342' & circulated 130 sxs. cement to the surface.

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 31 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING COMPANY, INC. INVOICE # 15338.

Plugged through: CSG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICE

DATE 8-31-04
INV. NO. 2005060469